

VGB Series

The AquaStar line of suction outlet covers, compliant with the new Virginia Graeme-Baker Pool and Spa Safety Act (ANSI/APSP 16-2011 AND NSF 50-2008)

Features

For single or multiple drain use (see installation instructions for plumbing, hydrostatic valve/drain pipe and single or multi-pump connections)

Single – 3" sump depth

Floor: 268 GPM at 3.1 fps

Wall: 172 GPM at 2.0 fps

Floor/Wall: 131 at 1.5 fps

27.9 square inch opening

#316 stainless steel screws

Manufactured from superior UV-resistant engineered polymers

Three ports: bottom 2½" OD, 2" ID S/S; inside 2" threaded FPT; two 2" threaded plugs included

Permanently attached gasket reduces gasket alignment problems

All components meet or exceed ANSI/APSP 16-2011 and NSF 50-2008 national standards and ASTM G154 UV testing exposure


Must use transitional glue when attaching to PVC pipe

Listed with IAPMO R&T

4 per case

The Unblockable![™]


NEW




Part # 32CDPHVxxx

Two drains in one!



STANDARD COLORS



OPTIONAL COLORS



VGB 2008 Compliant



1. 32" channel drain anti-entrapment suction outlet "pinhole" cover
2. 32" 3 port manufactured vinyl/fiberglass sump bucket
3. 32" channel drain vinyl clamping gasket
4. 2" npt plug
5. #10 x 1-1/4" flat head phillips type-a screw, 316 ss
6. 32" channel drain vinyl clamping ring w/ gasket
7. #10 x 1" flat head phillips type-a screw, 316 ss